BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of the Work: Improvements to drains of 4th main road of pampa extension to 5th main road of pampa extension in ward no.07, Byatarayanapura

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	2241.71	Removing and refixing stone slabs of drains and pointing in CM(1:3), with all lead and left as per directions of engineer in charge of the work.	Sqm	111.30	Rupees One Hundred Eleven and Thirty Paise Only
2	872.90	KSRRB 300-1. Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.. with all lead and left as per directions of engineer in charge of the work.	Cum	137.80	Rupees One Hundred Thirty Seven and Eighty Paise Only
3	282.42	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using **40mm** and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification . with all lead and left as per directions of engineer in charge of the work.	Cum	5421.90	Rupees Five Thousand Four Hundred Twenty One and Ninety Paise Only
4	12.60	KSRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications. with all lead and left as per directions of engineer in charge of the work.	Cum	5148.42	Rupees Five Thousand One Hundred Forty Eight and Forty Two Paise Only
5	64.80	KSRB 5.3-1:Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms hign, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications.with all lead and left as per directions of engineer in charge of the work.	Cum	4871.76	Rupees Four Thousand Eight Hundred Seventy One and Seventy Six Paise Only
6	108.00	KSRB 15.1.4: Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4. with all lead and left as per directions of engineer in charge of the work.	Sqm	148.40	Rupees One Hundred Forty Eight and Forty Paise Only
7	180.00	Providing and fixing 20 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing comlete as per specification with all lead and left as per directions of engineer in charge of the work.	Sqm	5418.00	Rupees Five Thousand Four Hundred Eighteen Only

8	1218.24	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.7.5 cm thick with all lead and left as per directions of engineer in charge of the work.	Sqm	742.00	Rupees Seven Hundred Forty Two Only
9	210.60	KSRB 5-14.1 : Providing and constructing load bearing wall with solid concrete blocks of size 400x100x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work.with all lead and left as per directions of engineer in charge of the work.	Sqm	859.66	Rupees Eight Hundred Fifty Nine and Sixty Six Paise Only
10	421.04	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete10cms thick.with all lead and left as per directions of engineer in charge of the work.	Sqm	966.72	Rupees Nine Hundred Sixty Six and Seventy Two Paise Only
11	1579.50	KSRB 5-8.1: Providing one line dressing to granite stone slabs/granite stone masonry as per specifications. with all lead and left as per directions of engineer in charge of the work.	Sqm	950.82	Rupees Nine Hundred Fifty and Eighty Two Paise Only
12	4680.00	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete.with all lead and left as per directions of engineer in charge of the work. 450x150x500 (1)	Nos	467.46	Rupees Four Hundred Sixty Seven and Forty Six Paise Only
13	2106.00	KSRB 5-9.1:Providing and applying ready mix priming coat over ocncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications. with all lead and left as per directions of engineer in charge of the work.	Sqm	39.22 (2)	Rupees Thirty Nine and Twenty Two Paise Only
14	410.00	Providing and fixing MS Grating 260x260 mm with all lead and left as per directions of engineer in charge of the work.	Nos	84.75 89.84	Rupees Eighty Nine and Eighty Four Paise Only
15	872.90	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 with all lead and left as per directions of engineer in charge of the work.	Cum	94.34	Rupees Ninety Four and Thirty Four Paise Only
16	42.00	KSRRB M2900-2.1. Laying Reinforced cement concrete pipe NP2 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications. MORTH Specification No. 2900 B. 1200 mm dia MORTH Specification No. 1000,2300 with all lead and left as per directions of engineer in charge of the work.	Mtr	5976.28	Rupees Five Thousand Nine Hundred Seventy Six and Twenty Eight Paise Only
17	3.56	Providing 100mm and down size nominal size. with all lead and left as per directions of engineer in charge of the work.	Cum	987.62	Rupees Nine Hundred Eighty Seven and Sixty Two Paise Only
18	1.58	Providing 40mm and down size nominal size with all lead and left as per directions of engineer in charge of the work.	Cum	1091.43	Rupees One Thousand Ninety One and Forty Three Paise Only

19	1.58	Providing 20mm and down size nominal size with all lead and left as per directions of engineer in charge of the work.	Cum	1091.43	Rupees One Thousand Ninety One and Forty Three Paise Only
20	1.19	Providing Fine aggrgate 2.36mm nominal size with all lead and left as per directions of engineer in charge of the work.	Cum	1054.29	Rupees One Thousand Fifty Four and Twenty Nine Paise Only
21	25.00	Providing and fixing MS Grating 260x260 mm with all lead and left as per directions of engineer in charge of the work.	Nos	89.84	Rupees Eighty Nine and Eighty Four Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಕಂಡಿಕೆ (22) ರಲ್ಲಿ ವಿವರಿಸಿರುವಂತೆ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು(BTP) ರವರು
ದೃಢೀಕರಿಸಿಕೊಳ್ಳುವ ಹಿನ್ನೆಲೆಯಲ್ಲಿ ಒಳಪಡಿಸಿ, ಟಿ.ಪಿ.ಆರ್
ಅನುಮೋದಿಸಿದೆ.
ಕರಡು ಟೆಂಡರ್ ಪೆಡ್ಯೂಲ್‌ನ್ನು ತಿದ್ದುಪಡಿ ಮಾಡುವಂತೆ
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ
ತಿದ್ದುಪಡಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ :
ರದ್ದುಗೊಳಿಸಿರುವ ಒಟ್ಟು ಐಟಂಗಳ ಸಂಖ್ಯೆ :
ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು (ಚುಲಪಂಕ)